

SURVEY & REMONUMENTATION

APR 27 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Chippewa</u> <small>(County)</small>	Located in:	Corner Code <u>F-13</u>
1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:24 P.M. RECEIPT# 1518
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
Register of Deeds Stamp & File Number
SHARON H. KENNEDY, REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

T46N R1W


I, William L. Karr, in a field survey on October 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-13) South 1/4 Corner Section 33, T.46 N., R.1 W. (Not common)

- 1840: Austin Burt set post Fir 10 N16E 26 Cedar 10 N39W 28
- 1898: County Surveyor notes call for 2627' for both 1/2 mile distances (2633.66' for the West 1/2 mile and 2630.63' for the East 1/2 mile today).
- 1977: J.H. Granger set a 1/2" iron in concrete for the North 1/4 corner of Section 4.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-13) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found no evidence of original corner. Found a 1/2" iron in concrete in approximate centerline of 12 Mile Road. Monument was set by Granger in 1977 as the North 1/4 corner for Section 4. An even split of S.C. 32/33 and S.C. 33/34 would place the South 1/4 corner of Section 33, 1.52' West of this monument. Many recent surveys have used this as the South 1/4 corner of Section 33. Based on current use and and close location to a single pro-rated position, I accepted the corner as found for the South 1/4 corner of Section 33. Corner falls 16.64' West of newly established North 1/4 corner of Section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-13) Corner is a 1/2" iron in concrete in approximate centerline of 12 Mile Road and 45' West of an old concrete culvert.

Witnesses: 6" Aspen	N36°E 41.75'
4" Aspen	S43°E 6.51'
12" Aspen	S22°W 11.12'
Transmission Pole(232)	S29°W 118.53'
4" Aspen	N41°W 75.21'
North 1/4 corner Section 4	East 16.64'



Signed by William L. Karr Date 12/21/94

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.