

MAR 09 1994

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 AM 10: 24

For corners in
Chippewa
(County)

Located In:	Corner Code #
T <u>46N</u> R <u>1W</u>	<u>G-1</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

J. Robin Matthe
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on May 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(G-1) Closing Corner Common to Sections 3 & 4 (T46N-R1W)

1845: J.H. Millett, set post 22 links West of Standard Corner.
6" Willow S73°E 18 links
12" Aspen N33°E 28 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron L.S. 27450 in a monument box. Corner has been used in many surveys. Originally re-established using previous centerline of Six Mile Road and old ties to the centerline railroad trestle in previous survey. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-1) Corner is a 1/2" iron L.S. 27450 in a monument box, 1' South of the centerline of Six Mile Road and 29.5' West of the centerline railroad bridge.

Witnesses:

Bridge Post	N50°E	29.82'
Guard Rail Post	S36°E	16.68'
Power Pole (With Soo Line Sign)	S58°W	128.36'
Guard Rail Post	N72°W	30.61'
Standard corner 33/34 (1/2" Iron L.S. 27450)	East	14.52'



Signed by William L. Karr Date 12/23/93
Surveyor's Michigan License No. 27450