

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

BOOK 10 PAGE 19
BOOK 10 PAGE 19
\$7.00 RECORDING FEE

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 1W

G-2

T R

T R

T R

T R

2. Property Controlling In Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



\$2.00 MSSR

3/3/1997 5:07:49 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

3/3/1997 5:07:56 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4	●	3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Keith R. Waters, in a field survey on 12/04 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G-2 1/4 Corner Common to Sections 3 & 4, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Fir 6, S26°E 26 links - Fir 4, S50°W 13 links.

1890 - County Surveyor Frederick H. Brown notes indicate corner was pro-rated between the original 1/4 corner at G-4 and a "Carleton corner" on the township line at G-1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program. Found no evidence of corner. Re-established corner on line between closing corner G-1 on the township line to the north and the section corner G-3 to the south, on the extension of a fence line to the west. A local landowner told me that the present fence was built in the same position as a previous fence, which was thought to have been built according the 1/4 post. The distances north and south fit fairly well with above mentioned Brown notes. I believe that the fence is the best available evidence of the corner as established by Brown.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap, on the east side of the north-south railroad tracks, which are on the east side of the Soo Line Road. Witnesses:

- Power Pole (E-10), N62°W 84.56'
- Center of Easterly Railroad Rail, WEST 20.65'
- 9" White Pine, S78°E 72.04' (side blaze only)
- 5" White Pine, N53°E 76.26' (side blaze only)

Note: Unless noted otherwise, distances are to a nail and tag in the side of the witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-96

Surveyor's Michigan License No. 33142

BOOK 10 PAGE 19