

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$7.00 RECORDING FEE

\$2.00 MSSR

3/3/1997 5:09:18 PM Receipt #275

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEED

BOOK 10 PAGE 23

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 09/08, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 Corner Common to Sections 15 & 16, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Fir 4, S65°W 19 links - Fir 3, S63°E 10 links.

1890 - County Surveyor Frederick H. Brown notes show corner midway between original section corners 2608 feet north and south.

1980 - Certificate of Survey, Thomas Kelly, R.L.S. 24599, shows west 1/4 corner of Section 15 at a distance of 2614.42 feet from the southwest corner of Section 15, and 5022.71 feet from the east 1/4 corner of Section 15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" x 18" smooth iron pin next to an old wood post. Iron is 2610.89 feet from section corner north, 2614.77 feet from section corner south, and is 1.6 feet east of a straight line between said section corners. The distance east to the east 1/4 corner of Section 15 checks with above mentioned Certificate of Survey. Accepted corner location as found and replaced the 1/2" iron pin with a 3/4" rebar and aluminum Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4 x 24" rebar and stamped Chippewa County Remonumentation cap on the east side of railroad tracks which are east of the Soo Line Road. Witnesses:

9" Spruce, S78°E 67.65'

14" Spruce, N38°W 42.18'

Power Pole (E-47), N52°W 169.38'

Centerline of Railroad Tracks, WEST 83.31'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 23

