

**SURVEY &
REMONUMENTATION**

APR 27 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 46N | R | 1W | G-7 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
19 DEC 94 10:17 A.M. RECEIPT# 1769
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

William L. Karr, in a field survey on October 19 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-7) Section Corner 15, 16, 21 & 22, T.46 N., R.1 W.

1845: J. Mullett set post corner to sections 15, 16, 21 & 22 Hemlock 20 S59W 23 lks Birch 18 N18E 19 lks

1941: Highway plans called for post with iron pin.

1960: MDOT found a boat spike in monument box(L.2,P.227)

1988: N.E. Hill (MDOT) found a boat spike buried deep in monument box with 3 rings raising box cover to surface. Re-set 3/4" pipe w/cap No.27447 and raised monument box to surface. Recorded in L.07, P.078.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:



(G-7) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found no evidence of original corner. Found 3/4" pipe w/cap No.27447 in monument box. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-7) Corner is a 3/4" pipe with cap No. 27447 in monument box.

Witnesses: Chiseled "x" in center of conc. H.wall N21°E 34.56'
P. Pole (MDOT tag) S30°E 68.97'
P. Pole (MDOT tag) S50°W 96.95'
Chiseled "x" on NE bolt of R.R. signal base S70°W 48.48'
Chiseled "x" on SE bolt of R.R. signal base N05°W 23.23'



Signed by William L. Karr Date 12/7/94
Surveyor's Michigan License No. 27450 723-12

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

