

MAY 28 1997 CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	G-9
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

\$7.00 RECORDING FEE

\$2.00 HSSR

3/3/1997 5:09:41 PM Receipt #275

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 24

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Corner Common to Sections 21, 22, 27, & 28, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Spruce 6, S50°E 12 links - Cedar 20, S46°W 34 links.

1899 - County Surveyor F.H. Brown indicates a "Carleton corner." No original evidence. Distance west to Railroad shown as 37 feet.

1925 - County Surveyor notes show a cement post. Witnesses: E'ly Rail - WEST 37.4' - Look Out Post, SW 25' - Large Pole, S21°E 27'.

1960 - J. Smallwood, Hwy. Dept., l., p. 243. Found iron pin. SW corner store, N50°E 51.28' - T. Pole, S20°W 32.14' - T. Pole, N 29.90'.

1983 - W.L. Karr, P.S. 27450, liber 6, page 95. Found two irons 2.82' apart. Accepted W'ly iron, which matched tie to store corner.

1991 - W.L. Karr, P.S. 27450, liber 7, page 383. Based on Railroad plans and County Surveyor notes, accepted the E'ly iron. Placed a monument box over found 3/4" iron. Witnesses: Power Pole (E-27), N08°W 31.81' - SW Corner of Old Store, N41°E 49.68' - Anchor Pole (E-2701), S05°W 31.58' - 1" Drift Pin, 2' below pavement, Due West 2.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 3/4" iron pin in a monument box approximately 2 feet south of the centerline of east-west asphalt road (10 Mile Road) and witness objects as called for in LCRC liber 7, page 383. This corner location has been in dispute for a number of years. The oldest available evidence is the ties to the railroad tracks as shown in the 1899 and 1925 County Surveyor notes, which support the easterly position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" iron pin in a monument box approximately 2 feet south of the centerline of 10 Mile Road, 37.48 feet east of the center of the easterly railroad rail of north-south tracks. Witnesses:

Power Pole, N08°W 31.78' (PK nail in west side)


Southwest corner of old store, N45°E 49.68' (corner of vinyl trim)

Anchor Pole (E-2701), S12°W 31.51' (PK nail in east side)

Center of northeast bolt on base of RR crossing sign, S80°W 57.16'

Center of northeast bolt on base of RR crossing sign, N45°W 33.10'

Note: Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 24