

MAY 28 1997

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T46N R 1W	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$7.00 RECORDING FEE

\$2.00 HSSR

3/3/1997 5:10:00 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 25

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 03/11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-11 Corner Common to Sections 27, 28, 33, & 34, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): White Pine 16, S47°W 22 links - Beech 14, S73°E 30 links.

1881, 1891 - County Surveyor Frederick H. Brown notes call out this corner as a "Carleton corner."

1902 - County Surveyor Frederick H. Brown notes say "put in post as the corner was being used."

1903 - County Surveyor Frederick H. Brown notes say "could not find any corner, drain tile and cedar post."

Circa 1920's - County Surveyor notes show small monument and cedar post. Distance west to R.R. tracks shown as 116 feet.

1959 - Ray Walker, Highway Department, liber 3, page 226, Chippewa County corner records. Iron pin in cedar post.

1960 - John Smallwood, Highway Department, liber 3, page 226, Chippewa County corner records. Found iron pin in cedar post.

Witnesses: P. Pole, N60°W 64.00' - Guy Pole, S70°W 87.72' - Fence Post, South 35.17' - Iron RR Post, N75°W 80.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron pin in a cedar post and a Highway Department tag in a power pole to the northwest. Other record witnesses are gone. Centerline of railroad tracks is 119 feet west, old County Surveyor notes show 116 feet, distance appears to be to the easterly rail. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron pin in a cedar post in the approximate centerline of east-west gravel road (11 Mile Road).

Witnesses:

Power Pole (DR4-39-50), N02°E 29.54'


Power Pole, N60°W 64.00' (Highway Department nail and tag)

Power Pole, N82°E 184.93'

6" Aspen, S15°E 106.06'

Centerline of Railroad Tracks, WEST 119'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 25