

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

93 DEC 29 AM 10:24

J. Roger Maloth
REGISTER OF DEEDS

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>H-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on December 11, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(H-1) North 1/4 Corner Section 3 (T46N-R1W)

Not set in original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(H-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Corner was placed on a line between the standard corner of Sections 33 & 34 and the South 1/4 of Section 34. Range was established by a fence line to the South in previous survey. Accepted corner position as found.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(H-1) Corner is a 1/2" x 24" pin with L.S. cap. Corner falls 3'± South of the Centerline of Six Mile Road.

Witnesses:

Wood Post (With Telephone Box)	N64°E	105.54'
Power Pole (E34)	S62°E	121.34'
Power Pole (E35)	S75°W	145.53'
6" Spruce	N85°W	176.84'
South 1/4 Corner of Sec 34	East	6.31'

Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

