

MAY 28 1997 CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 RECORDING FEE


\$2.00 MSSR

3/3/1997 5:11:08 PM Receipt #27
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

For corners in

Chippewa Located In: Corner Code #
(County)

- 1. Public Land Survey T46N R 1W H-3
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R



BOOK 10 PAGE 27

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/06, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3								●					
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-3 1/4 Corner Common to Sections 3 & 10, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Spruce 10, S21°W 11 links - Fir 6, N12°E 14 links.
1892 - Drawing of Section 3 by County Surveyor Frederick H. Brown shows this corner 2624 feet from section corner to the west and 2631 feet from section corner to the east. No other information is given.
Date unknown - County Surveyor Frederick H. Brown notes state "this 1/4 post was gone and in the burnt land." Drawing of Section 10 shows a distance between Sections 3 & 10 of 5255 feet. The distance on the east 1/2 mile is shown as 2635 feet, no distance is shown on the west 1/2 mile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.
Found no evidence of corner. Re-established corner on line between section corners 2630.12 feet east and 2590.67 feet west, on the extension of a fence line to the north. The distance to the section corner east is close to above mentioned Brown notes, it appears that fence was built according to a corner as established by Brown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap on the extension of a fence line to the north.
Witnesses:
4" Spruce, S70°E 46.06'
Fence Post, N27°E 26.36'
Fence Post, N06°W 20.75'
5" Aspen, N75°W 66.22'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 27

