

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 1W H-9

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9 1/4 Corner Common to Sections 22 & 27, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Spruce 10, N12°W 25 links - Spruce 4, S49°E 15 links.

1902 - County Surveyor Frederick H. Brown notes indicate corner midway between section corners 5243 feet apart.

1983 - William L. Karr, P.S. 27450, LCRC liber 6, page 110, Chippewa County corner records. Set 1" drill rod on line between section corners east and west, on the extension of a fence line to the north. Witnesses: Power Pole, N84°E 197.60' - Corner Fence Post, N02°E 90.74' - End Guard Rail Post, S53°E 48.01' - East Range of House, WEST 61.65'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1" drill rod in the centerline of 10 Mile Road as called for in 1983 LCRC. Position checks well with distances as shown in above mentioned Frederick H. Brown notes. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" drill rod in the centerline of east-west asphalt road (10 Mile Road), on the easterly approach to the overpass over Highway I-75). Witnesses:

Spike in Top of End Guard Rail Post, S53°E 48.57'

Nail and tag #331423 Power Pole (E9), N87°E 196.05'

Center of Top of Westerly Chain Link Fence Corner (fence around guy wire), N48°E 103.03'

East Range of House, WEST 61.65'

Note: Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

33142

Surveyor's Michigan License No. _____

Date 12-30-96

\$7.00 RECORDING FEE


\$2.00 NSSR

3/3/1997 5:11:59 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 29

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9								●					
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



BOOK 10 PAGE 29