

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 RECORDING FEE

\$2.00 MSSR

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	H-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

3/3/1997 5:12:32 PM Receipt #2
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 30

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 03/05, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1/4 Corner Common to Sections 27 & 34, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Birch 10, S70°W 14 links - Black Ash 12, N08°W 23 links.
1881, 1902 - County Surveyor Frederick H. Brown notes show this corner midway between section corners 2625 feet east and west.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program. Found no evidence of corner. Re-established corner on line between section corners 2632.66 feet east and 2625.30 feet west, on the extension of the remains of an old fence line to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4 x 24" rebar with a plastic Chippewa County Remonumentation cap in the approximate centerline of an east-west gravel road (11 Mile Road), on the extension of an old fence line to the south. Witnesses:
Power Pole (208), N34°E 43.13'
Power Pole (DR4-39-61), S04°W 31.78'
Power Pole (DR4-39-60), S84°W 243.25'
7" Aspen, N68°W 59.47'



Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 30