

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

BOOK 10 PAGE 32

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	1-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$7.00 RECORDING FEE

\$2.00 NCSR

3/3/1997 5:13:14 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 08/16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3								●				
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1-3 Corner Common to Sections 2, 3, 10, & 11, Town 46 North, Range 1 West  
1845 - Original ties (James Mullett): Birch 10, N54°E 19 links - Cedar 18, S60°W 43 links.  
1892, 1898 - County Surveyor Frederick H. Brown indicates no evidence of original corner, being in an area of clearing and burning. He re-established the corner by pro-rating between town line to the north and original 1/4 corner 1/2 mile south.  
Circa 1920's - County Surveyor notes show corner with various fence witnesses.  
Date unknown - Chippewa County Road Commission, liber 2, page 190, Chippewa County corner records. 3/4" iron pipe.  
1960 - John Smallwood, Highway Department, liber 3, page 236, Chippewa County corner records. Found 3/4" iron pin.  
1991 - Lawrence E. Weinreis, P.S. 32343, LCRC in liber 8, page 282, Chippewa County corner records. Found 3/4" iron pin and one Highway Dept. witness. Witnesses: Power pole (DR3-53-9), N52°E 48.61' - 5" Spruce, S49°W 70.72' - Fence post, N22°W 36.29'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found a 1" iron pin and three witness objects as called for in LCRC liber 8, page 282. North-south position is consistent with above mentioned Frederick H. Brown notes. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" iron pin in approximate centerline of north-south gravel road (Elm Road), at centerline of 2 track roads to the east and west. Witnesses:  
Power Pole (DR3-53-9), N52°E 48.91' (nail and tag #32343)  
6" Spruce, S56°W 70.72' (nail and tag #32343)  
Fence Post, N53°W 36.29' (nail and tag #32343)  
8" Tamarack, S31°E 105.37' (nail and tag #33142)

Note: Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 32

