

**SURVEY &  
REMONUMENTATION**

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

**MAY 28 1997**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

**\$7.00 RECORDING FEE**

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	I-5
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**\$2.00 MSSR**

3/3/1997 5:14:03 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

**BOOK 10 PAGE 34**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 09/16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5									●				
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-5 Corner Common to Sections 10, 11, 14, & 15, Town 46 North, Range 1 West  
1845 - Original ties (James Mullett): Tamarack 10, N22°E 60 links - Tamarack 8, N15°W 106 links  
1898, 1902 - County Surveyor Frederick Brown indicates an original corner with original bearing tree.  
Circa 1920's - County Surveyor notes show corner with assorted witnesses.  
Date unknown - Chippewa County Road Commission, liber 2, page 190, Chippewa County corner records. 1" iron pin.  
1960 - John Smallwood, Highway Department, liber 2, page 227, Chippewa County corner records. Found ¾" iron pipe.  
1991 - Lawrence E. Weinreis, P.S. 32343, LCRC in liber 8, page 221, Chippewa County corner records. Found a ¾" iron pin.  
Witnesses: Fence Post, S80°E 121.93' - Power Pole (DR3-35-5), S23°E 137.68' - 18" Willow, S18°E 89.12'  
"V" in North End of 24" Steel Culvert, N87°W 64.49'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found a 1" iron pin and the fence post, power pole, and willow (dead) witnesses as called for in LCRC liber 8, page 221.  
The culvert has been replaced. Accepted corner as found and established new witness objects.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is a 1" iron pin at the approximate centerline P.I. of Elm Road to the north and 8 Mile Road to the west. Witnesses:

Fence Post, S80°E 121.89' (nail and tag #32343)  
Power Pole (DR3-35-5), S23°E 137.54' (nail and tag #32343)  
5" Spruce (N'y spruce in row on east side of I-75 R.O.W. fence), N82°E 142.70'  
6" Spruce (S'y spruce in row on east side of I-75 R.O.W. fence), S50°E 134.46'

Note: Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

**BOOK 10 PAGE 34**