

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	I-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

\$7.00 RECORDING FEE

\$2.00 HSSR

3/3/1997 5:14:23 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 35

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/06, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-6 1/4 Corner Common to Sections 14 & 15, Town 46 North, Range 1 West

1845 - Original corner (James Mullett) was a 10" Fir.

Circa 1902 - Section drawings by County Surveyor Frederick H. Brown indicate a random line run between Sections 14 and 15, with a total distance shown as 6232 feet, with a distance of 3116 feet shown on the south 1/2 mile. A distance of 5020 feet is shown on the east-west 1/4 line of Section 15.

1980 - Certificate of Survey, Thomas Kelly, R.L.S. 24599, shows this corner at a distance of 5022.67 feet from the West 1/4 corner of Section 15.

1993 - Certificate of Survey, William L. Karr, P.S. 27450, shows this corner as a found iron pipe at a distance of 3111.55 feet from the Southeast corner of Section 15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 3/4" iron pipe next to an old squared cedar post. Distances to the West 1/4 corner and Southeast corner of Section 15 check with above mentioned Certificate of Surveys and are also very close to those as shown in the Frederick H. Brown notes.

Accepted corner as found and established witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" iron pipe next to an old squared cedar post. Witnesses:


4" Poplar, S32°W 132.53' (nail and tag #33142)

4" Spruce, N70°W 145.91' (nail and tag #22428)

7" Elm, N48°W 132.00' (nail and tag #22428)

6" Deciduous Tree (species unknown), (nail and tag #22428)

Note: Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 35