

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 RECORDING FEE

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	I-9
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

\$2.00 MSSR

3/3/1997 5:14:50 PM Receipt #275
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 36

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Corner Common to Sections 22, 23, 26, & 27, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Birch 20, N40°E 35 links - Birch 16, S60°W 60 links.

1889, 1892, 1902 - County Surveyor Frederick H. Brown indicates an iron bolt as established by Carleton.

Circa 1920's - County Surveyor notes indicate a large cedar post, 3"-4" iron bolt, and cement post at corner location.

1959 - Ray Walker, Highway Department, liber 3, page 225, Chippewa County corner records. Found 1/2" iron rod in pavement.

1960 - John Smallwood, Highway Department, liber 2, page 243, Chippewa County corner records. Found 3/4" iron pin.

1983 - William L. Karr, P.S. 27450, LCRC liber 6, page 110, Chippewa County corner records. Found a 3/4" iron pipe and a pole in the NE quadrant as called for in Highway Department records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 3/4" iron pin in the centerline of 10 Mile Road (asphalt). Also found four witness objects as called for in LCRC in liber 6, page 110. Distances to other recovered corners in the area check well with above mentioned Frederick H. Brown notes from the late 1800's and early 1900's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" iron pin the centerline of 10 Mile Road (asphalt). Witnesses:

Highway Department nail and tag in cut off power pole, N46°E 46.43'

PK nail in power pole (E10201), S81°W 222.20'

PK nail in power pole (E102), N75°W 214.81'

Center of Michigan Bell box, S42°E 46.40'

Note: Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
 Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 36