

MAY 28 1997

**COMMISSIONER CHIPPEWA COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 RECORDING FEE

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T 46N	R 1W	I-11
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

\$2.00 MSSR

3/3/1997 5:15:09 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 37

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 05/30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11 Corner Common to Sections 26, 27, 34, & 35, Town 46 North, Range 1 West  
1845 - Original ties (James Mullett): Spruce 10, N58°E 17 links - Spruce 8, S29°W 39 links.  
1881, 1889, 1902 - County Surveyor Frederick H. Brown notes state "a Carleton corner, don't think he saw any original marks."  
Circa 1920's - County Surveyor notes indicate a cedar post and monument. Witnesses: 6" Poplar, S35°W 27' - 6" Birch, S30°E 26'.  
1960 - John Smallwood, Highway Department, liber 2, page 258, Chippewa County corner records. Found concrete monument post.  
Witnesses: Fence corner, N35°E 36.55' - Fence corner, N04°E 29.21' - 12" White birch, S30°E 50.79'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found an old concrete monument in the approximate centerline of an east-west gravel road, 1 foot below surface. All previous witnesses mentioned above are gone. Accepted corner as found and established new witness objects.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is a 3/2" diameter concrete monument in the approximate centerline of east-west gravel road (11 Mile Road).  
Witnesses:  
6" Spruce, S53°W 59.25'  
8" White Birch, S14°W 92.82'  
6" White Birch, S34°E 49.27'  
9" White Birch, S56°E 65.50'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 37

