

MAY 28 1997

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 RECORDING FEE

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T46N R 1W	I-12
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$2.00 N SSR

3/3/1997 5:15:30 PM Receipt #275  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 38

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 05/30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4			3		2			1
3													
4	7	8			9			10		11			12
5													
6	18	17			16			15		14			13
7													
8	19	20			21			22		23			24
9													
10	30	29			28			27		26			25
11													
12	31	32			33			34	●	35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 I-12 1/4 Corner Common to Sections 34 & 35, Town 46 North, Range 1 West  
 1845 - Original ties (James Mullett): Cedar 4, N63°E 35 links - Spruce 4, S79°W 10 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.  
 Found no evidence of corner. Re-established corner by single proportionate measurement between section corner I-11 to the north and standard corner I-13 on the township line to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap.

- Witnesses:
- 6" Spruce, EAST 3.89'
  - 7" Spruce, S22°W 9.18'
  - 5" White Birch, S64°W 7.90'
  - 9" White Birch, N04°E 22.63'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters  
 Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 38