

MAR 09 1994

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE

93 DEC 29 AM 10:24

Filing Requirement of Act 74, Mich. P.A. 1970

*J. Roger Mallett*  
REGISTER OF DEEDS

For corners in

Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 46N R 1W      K-1
- T     R
- T     R
- T     R
- 2. Property Controlling    S     T     R
- in Section               S     T     R
- 3. Miscellaneous           S     T     R
- Property in Sec.         S     T     R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-1) Closing Corner Common to Sections 1 & 2 (T46N-R1W)

1845: J.H. Mullett, D.S. - set post 12 links West of Standard Corner  
10" Birch           S24°E       22 links  
12" Maple           S30°W       56 links

1960: J.P. Smallwood, Michigan Highway Department.  
Recorded as Common Corner in Liber 3, Page 236 of the Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1 1/4" O.D. pipe with PK nail in it. Pipe fell on the extension of a fence line to the South. Corner was determined to be Closing Corner 2/1. Distance West to the North 1/4 corner of Section 2 matched quite closely with old County Surveyor distance. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-1) Corner is a 1 1/4" O.D. pipe with PK nail in center. Falls on approximate centerline of Six Mile Road on the extension of a field line to the South.

Witnesses:

- Power Pole (126/1)           N79°E       176.94'
- Standard Corner 35/36       East        7.92'
- Power Pole                   S75°E       157.61'
- Corner (Metal) Fence Post   South       38.98'
- Corner (Metal) Fence Post   S46°W       63.19'
- Anchor Pole (126/2)         N40°W       34.53'

Signed by William L. Karr

Date 12/29/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.

