

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 RECORDING FEE

For corners in

Chippewa
(County)

Located In:	Corner Code #
T46N R 1W	K-5
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

\$2.00 MSSR

3/3/1997 5:17:54 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

BOOK 10 PAGE 45

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 08/20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
K-5 Corner Common to Sections 11, 12, 13, & 14, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Birch 10, S77°E 11 links - Birch 8, N46°W 11 links.
1895, 1898, 1905 - County Surveyor Frederick H. Browns indicates that he set a large cedar post from original bearing trees.
1983 - William L. Karr, P.S. 27450, as recorded in liber 6, page 382, Chippewa County corner records. Set 1/2" iron on fence lines north and south, midway between end fence posts. Witnesses: 3" W. Birch, N22°E 33.68' - Power Pole (290/3.3), S79°E 179.35', 6" W. Birch, N65°W 82.29'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron pin with cap #27450 and two of the witnesses as shown on LCRC liber 6, page 382. Distances to other re-established corners north, south, east, and west all check well with those as shown in above mentioned Frederick H. Brown notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron pin with plastic cap #27450, approximately 3 feet north of the centerline of an east-west gravel road (8 Mile Road). Corner is 5.5 feet west of a north-south CMP culvert under the road. Witnesses:
MBT Pole, S79°E 179.30'
5" White Birch, N22°E 33.33'
6" White Birch, N54°E 33.57'
Corner Fence Post, SOUTH 35.88'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 45