

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 RECORDING FEE

For corners in

Chippewa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------------|-----|
| 1. Public Land Survey | T ^{46N} R ^{1W} | K-8 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

\$2.00 MSSR

3/3/1997 5:19:11 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 47

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on 09/10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 Corner Common to Sections 23 & 24, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Black Ash 16, S44°W 07 links - Fir 6, S08°E 18 links.

1892, 1897 - County Surveyor notes (Frederick H. Brown) show corner midway between section corners 2708 feet north and south.

1995 - Certificate of Survey, RLS 22428, shows East 1/4 corner of Section 23 as a 1/2" rod at fence corner. Witnesses:

Fence post, SOUTH 14.80' - Fence post, EAST 11.19' - Fence post, NORTH 14.75' - Fence post, WEST 6.37'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron rod at a fence corner. Also found the four witness objects as shown in above mentioned Certificate of Survey. The distance from the 1/2" iron to the section corner north is 2709.53 feet and the distance to the section corner south is 2712.93 feet, which fits fairly well with above mentioned Frederick H. Brown notes from the late 1800's. Corner is 2.8 feet west of a straight line between said section corners north and south. Accepted corner location as found and replaced the 1/2" iron with a 3/4" x 24" rebar and plastic Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap at a fence corner. Witnesses:

Nail and tag #22428 in fence post, SOUTH 14.80'

Nail and tag #22428 in fence post, EAST 11.19'

Nail and tag #22428 in fence post, NORTH 14.75'

Nail and tag #22428 in fence post, WEST 6.37'



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 47