

MAY 28 1997

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 1W

K-9

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

BOOK 10 PAGE 48

\$7.00 RECORDING FEE

\$2.00 MSSR

3/3/1997 5:19:29 PM Receipt #275

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 11/11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner Common to Sections 23, 24, 25, & 26, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Spruce 20, N33°E 33 links - Maple 12, S62°W 44 links.

1889, 1892, 1895, 1897 - County Surveyor notes from Frederick H. Brown indicate that corner was re-established by digging up the 3 miles between original section corners at K-5 and K-11.

Circa 1920's - County Surveyor notes indicate a cedar post and cement monument.

Witnesses: Gas pipe, North 29 feet - 8" Spruce, S32°W 66' - Pole, N57°E 38'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" x 24" rebar at the intersection of east-west gravel road (10 Mile Road) at seasonal road (Balsam Road) to the south, on the extension of a fence line to the north. Location fits well with distances as shown in above mentioned Frederick H. Brown notes from the late 1800's. Accepted corner location as found and replaced the 1/2" rebar with a 3/4" x 24" rebar and plastic Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap at the intersection of 10 Mile Road and Balsam Road.

Witnesses:

Power Pole (DR2-743-35), N44°W 52.24'

Power Pole (D-35), S46°W 56.15'

9" Spruce, S74°E 145.65'

8" Spruce, S40°E 91.70'

Note: Distances are to a nail/tag #33142 in the side of witness object. Bearings are compass bearings corrected for declination.

Trees are blazed and painted.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 48

