

SURVEY &  
 REMONUMENTATION  
 MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                    |             |               |
|------------------------------------|-------------|---------------|
| Chippewa                           | Located In: | Corner Code # |
| (County)                           |             |               |
| 1. Public Land Survey              | T46N R 1W   | K-11          |
|                                    | T R         |               |
|                                    | T R         |               |
|                                    | T R         |               |
| 2. Property Controlling in Section | S T R       |               |
|                                    | S T R       |               |
| 3. Miscellaneous Property in Sec.  | S T R       |               |
|                                    | S T R       |               |

\$7.00 RECORDING FEE

\$2.00 MSSR

3/3/1997 5:20:06 PM Receipt #275  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 50

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 04/18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

K-11 Corner Common to Sections 25, 26, 35, & 36, Town 46 North, Range 1 West  
 1845 - Original ties (James Mullett): Hemlock 20, S25°W 28 links - Tamarack 18, N40°W 29 links.  
 1889, 1898, 1902 - County Surveyor notes from Frederick H. Brown indicate an original corner with bearing tree standing.  
 Circa 1920's - County Surveyor notes indicate a small cement post at corner location. Witnesses: Fence corner NW 41 feet, Fence corner NE 44 feet, Gas pipe South 32 feet.  
 1965 - John Smallwood, Highway Department, L. 2, P. 216, Chippewa County corner records. Found 6" wood post buried in road. Witnesses: Fence corner, South 31.37' - P. Pole, N45°W 57.30' - Fence corner, N45°E 44.45'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
 Found a 3" diameter concrete monument with thin wire in the center next to an old wooden post buried in the intersection of 11 Mile Road east and west (gravel) at Balsam Road (seasonal) to the north. Also found a Highway Department nail and tag in a power pole as called for in Liber 2, page 216. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3" diameter concrete monument in the intersection of 11 Mile Road and Balsam Road. Witnesses:  
 Power Pole (DR2-74-17), N34°W 57.57'  
 Power Pole, N77°E 194.37'  
 Power Pole (D-52), S10°W 195.82'  
 Fence Post, S61°E 57.35'

Note: Distances are to a nail/tag #33142 in the side of witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters  
 Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 50

