

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 AM 10:24

*J. Roger Malott*  
REGISTER OF DEEDS

For corners in  
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(L-1) North 1/4 Corner of Section 1 (T46N-R1W)

Corner was not established in original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(L-1) This corner is being established as part of the Chippewa County Remonumentation Program.

Corner was established midway between the Northeast and Northwest corners of Section 1 on the Township line between the South 1/4 corner of Section 36 and the Standard Corner 35/36. Corner falls 7.6' West of a North-South fence in Section 1, which is consistent with County Surveyor notes from the early 1900's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(L-1) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap on the approximate centerline of Six Mile Road.

Witnesses:

11" White Pine	N60°E	125.36'
South 1/4 Corner of Section 36	East	3.96'
12" Scotch Pine	S17°E	62.79'
"V" Notch in North End of 40" C.M.P.	S47°W	63.22'
14" Maple	N48°W	85.28'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.