

MAY 28 1997

COMMISSIONER CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located in:	Corner Code #
1. Public Land Survey	T46N R 1W	L-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$7.00 RECORDING FEE

\$2.00 MSSR

3/3/1997 5:20:46 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 52

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 08/20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


L-3 1/4 Corner Common to Sections 1 & 12, Town 46 North, Range 1 West  
1845 - Original ties (James Mullett): Birch 10, N58°W 08 links - Black Ash 4, S15°E 19 links.  
1895 - County Surveyor Frederick H. Brown indicates a large cedar stake midway between section corners 2608 feet east and west.  
1985 - Larry R. Rogers, P.S. 29251, liber 6, page 291, Chippewa County corner records. Re-established position on line between the NW and NE corners of Section 12, on the extension of a fence line to the north. Distances check with County Surveyor notes.  
Witnesses: Corner fence post, N03°E 30.15' - Power pole, S69°E 156.61' - Corner fence post, S27°W 63.64' - 10" Spruce, N73°W 116.65'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1" iron pipe and three witness objects as called for in LCRC liber 6, page 291. Corner is on line between recovered section corners 2611.48 feet east and 2608.50 feet west, which is very close to above mentioned County Surveyor notes. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" iron pipe in the approximate centerline of 7 Mile Road (gravel) on the extension of a fence line to the north, approximately 29 feet east of a fence line to the south. Witnesses:  
PK nail in leaning corner fence post, N03°E 30.44'  
PK nail in leaning corner fence post, S34°W 63.88'  
Nail and tag #33142 in Power Pole, S64°E 156.52'  
Nail and tag #33142 in Power Pole, S76°W 160.27'  
Nail and tag #33142 in 5" Spruce on north-south fence line, S15°W 173.62'  
Note: Bearings are compass bearings corrected for declination. Spruce is blazed and painted.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 52