

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 RECORDING FEE

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T46N R 1W	L-9
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$2.00 MSSR

3/3/1997 5:21:43 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 54

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 04/12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1/4 Corner Common to Sections 24 & 25, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Black Ash 10, S08°W 22 links - Fir 6, N14°E 18 links.
1895, 1897 - County Surveyor notes (Frederick H. Brown) show corner midway between section corners 2654 feet east and west.
1965 - John P. Smallwood, Michigan State Highway Department, as recorded in liber 2, page 261, Chippewa County corner records. Found 6" wood post buried in road. Witnesses: Fence post, S30°W 46.30' - Fence post, Due south 34.99' - Fence post, Due north 32.86'. Distance to the section corner east is shown as 2647.34 feet.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron pin in remains of a wooden post buried in the approximate centerline of an east-west gravel road (10 Mile Road).
Also found a Highway Department nail and tag in a fence post to the south as called for in liber 2, page 216. The distance to the section corner east also checks well with Highway Department records. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron pin in a wooden post in the approximate centerline of 10 Mile Road. Witnesses:
3" Spruce, S24°W 71.22'
6" Elm, S43°W 79.34'
Fence Post, N31°W 36.26'
Fence Post, S05°W 34.78' (Highway Department nail and tag)

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 54