

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 RECORDING FEE

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 1W

L-11

2. Property Controlling in Section

S

T R

3. Miscellaneous Property in Sec.

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

\$2.00 MSSR

3/3/1997 5:21:59 PM

Receipt #275

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 55

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters

04/18

96

in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1/4 Corner Common to Sections 25 & 36, Town 46 North, Range 1 West

1845 - Original notes (James Mullett) indicate a 4" Maple for 1/4 corner.

1895, 1898 - County Surveyor notes from Frederick H. Brown show 1/4 corner midway between original section corners 2674 feet east and 2674 feet west.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Re-established corner by single proportionate measurement on line between section corners 2677.56 feet east and 2677.56 feet west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap approximately 4 feet south of the centerline of an east-west gravel road (11 Mile Rd.) at the east edge of a gravel drive to the north. Witnesses:

Power Pole (DR2-74-10), N73°W 132.69'

6" Apple in clump, N42°W 39.44'

10" Apple in clump, N79°E 132.54'

Power Pole, N85°E 289.14'

Note: Distances are to a nail/tag #33142 in the side of witness object. Trees are not blazed.

Signed by Keith R. Waters

Date 12-30-96

Surveyor's Michigan License No. 33142

BOOK 10 PAGE 55

