

# SURVEY & REMONUMENTATION

APR 27 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Chippewa</u> <small>(County)</small>	Located In:	Corner Code $\neq$	
1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>L-13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

\$ 7.00 LAND CORNER  
\$ 2.00 NSSR  
5 DEC 94 12:25 P.M. RECEIPT# 1518  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS  
**Register of Deeds Stamp & File Number**

I, William L. Karr, in a field survey on October 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the published of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

T46N R1W

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(L-13) South 1/4 Corner Section 36, T.46 N., R.1 W. (Not common)

1840: Austin Burt set post. Cedar 12 N40E 22 Cedar 6 N16W 12


1910: County Surveyor notes show the corners along the Township line as common. Distance for East 1/2 mile was 2660' (2640.66' today).

1982: W.L. Karr set a 1/2"x 18" iron w/cap No. 27450, 5.94' West (GLO is 5.94') of the North 1/4 Corner of Section 1, which was established using a North-South 1/4 line fence in Section 1. A 1/2" pin w/cap No. 27450 was set at the North 1/4 corner of Section 1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-13) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found no evidence of original corner. Found the 1/2" pin w/cap No. 27450 as set in 1982, 5.94' West of the North 1/4 corner of Section 1. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-13) Corner is a 1/2" pin w/cap No. 27450, 2' North of the centerline of 12 Mile Road.

Witnesses: 12" Aspen	N02°E	25.49'
8" Spruce	N19°E	31.53'
6" Cedar	S27°E	39.04'
12" Balsam Fir	S06°E	33.80'
Fence Post	S56°W	56.96'
10" Aspen	N13°W	42.25'
North 1/4 Corner Section 1 East		5.94'



Signed by William L. Karr Date 12/2/94

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.