

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: Corner Code #

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:11

J. Roger Marlette

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 46N R 1E A-7 Same
T 46N R 1W M-7 Corner
- 2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters, in a field survey on OCTOBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-7) Northwest Corner of Section 19 (T46N-R1E)

Original Notes: Set post corner of Sections 13 and 24

Tamarack 8 S49W 31 links Spruce 10 N08W 49 links

Subsequent Restoration, May 14, 1971, Chippewa County Road Commission recorded L.3, P.204

Corner Records. Found Cedar post and iron pipe. 3/4" Iron Pipe 33' Due North

TK Corner Fence Post 44.30' Southeast TK Telephone Pole 48.10' Northeast

1985: L.R. Rogers found 3/4" pipe and accepted (Liber 6, Page 287).

Corner Fence Post Due North 49.54' Anchor Pole N31°E 57.41'

Power Pole (DR1/45) S28°E 56.58' Corner Fence Post S29°W 58.72'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-7) Found corner and all accessories as recorded in Liber 6, Page 287 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-7) Corner is a 1" bar in a monument box in the centerline of East-West asphalt road (9 Mile) on the extension of a fence line to the North.

Witnesses:

Corner Fence Post	Due North	49.54'
Anchor Pole	N31°E	57.41'
Power Pole (DR1/45)	S28°E	56.58'
Corner Fence Post	S29°W	58.72'



Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.