

1993

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

93 DEC -3 PM 3:59

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Chippewa

*J. Roger Malott*  
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 1E T 46N R 1W T _____ R _____ T _____ R _____	A-10 Same M-10 Corner
2. Property Controlling In Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Keith R. Waters in a field survey on June 14, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10 (T46N, R1E)  
1/4 Corner Common to Section 30, T46N, R1E and Section 25, T46N, R1W

Michigan State Highway Department (11-29-65) as recorded in liber 2, page 223, of Chippewa County corner records: Found 1/2" reinforcing rod in MSHD monument box with the following ties: Fence Post, Due West 72.99'  
Center ROW Marker, S80°E 74.70'  
Power Pole, N65°E 77.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 (T46N, R1E)  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found a 1/2" iron pin in a monument box 0.5' east of centerline of Highway M-129 on line with a fence to the west. Distance to Highway Department nail and tag in corner fence post checks within 0.06' of record. Distances to Section corners 1/2 mile north and 1/2 mile south check closely with those as shown on Highway Departments records. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 (T46N, R1E)  
Corner is a 1/2" iron pin in a monument box 0.5' east of centerline of Highway M-129 at a fence line to the west.

Witnesses:  
P. Pole, N72°E 76.76'  
Chiseled "X" in top south end of 18" conc. culvert, S79°E 61.91'  
MSHD nail/tag in old corner fence post, West 73.05'  
Fence Post, S51°W 97.54'

Note: Unless noted otherwise, distances are to a nail and tag in the side of the witness object. Bearings are compass bearings corrected for declination. Distances measured with EDM.



Signed by *Keith R. Waters*

Date 11-30-93

Surveyor's Michigan License No. 33142