

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 LAND CORNER  
 Chippewa County Remonumentation Corner

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R1E T46N R2E	M-8 Same A-8 Corner
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

\$2.00 MSSR  
 2/28/1997 2:52:48 PM Receipt #217  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 353

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	25	24	23	22	21	20							
11													
12	26	25	24	23	22	21							
13													
14	27	26	25	24	23	22							
15													
16	28	27	26	25	24	23							
17													
18	29	28	27	26	25	24							
19													
20	30	29	28	27	26	25							
21													
22	31	30	29	28	27	26							
23													
24	32	31	30	29	28	27							
25													
26	33	32	31	30	29	28							
27													
28	34	33	32	31	30	29							
29													
30	35	34	33	32	31	30							
31													
32	36	35	34	33	32	31							

I, William L. Karr, in a field survey on November 13, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-8) 1/4 Corner Common to Section 24, T. 46 N., R. 1 E., and Section 19, T. 46 N., R. 2 E.

1845 J.H. Mullett set post in marsh in original survey - no witnesses available.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-8) 1/4 Corner Common to Section 24, T. 46 N., R. 1 E., and Section 19, T. 46 N., R. 2 E.  
 This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Could find no evidence of the original corner or subsequent restoration.

Reestablished the corner on the extension of the line between sections 25 and 30 to the South, and at the record GLO distance North of the section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-8) 1/4 Corner Common to Section 24, T. 46 N., R. 1 E., and Section 19, T. 46 N., R. 2 E.

Corner is a 3/4" x 48" re-rod with stamped aluminum Chippewa County Remonumentation Cap. Corner is set in open marshy area and is 1' above ground.

Witnesses:	Wood Post	North	3.00'
	Meander Corner	N 01° 11' 01" W	660.00'
	Section Corner	S 01° 11' 01" E	2640.00'
	Meander Corner on	N 29° 34' 00" W	2994.17'
	North Section Line		

Bearings are grid bearings based on the Michigan State Plane Coordinate System, North Zone. Distances are actually measured distances to adjacent corners. No other acceptable ties available.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

