

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970.00 LAND CORNER  
Chippewa County Remonumentation Corner

COMMISSION

For corners in

Chippewa County

Located in:

Corner Code #

1. Public Land Survey

T46N R1E

M-9 Same

T46N R2E

A-9 Corner

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

\$2.00 MSSR

2/28/1997 2:51:47 PM

Receipt #217

RECEIVED FOR RECORD

CHIPPewa COUNTY - STATE OF MICHIGAN  
BARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 352

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	50		29		28		27		26		25		
11													
12													
13													
14													

I, William L. Karr, in a field survey on December 4, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-9) Section Corner Common to Sections 24 & 25, T. 46 N., R. 1 E., and Sections 19 & 30, T. 46 N., R. 2 E.

1845 J.H. Mullett set post in original survey.

1910 A field book in the County Surveyors Office, shows the South line of section 24 as 5287'. The notes do not mention what the corner is.

1960 Supervisors Plat No. 1 of Bruce Township, recorded Liber 7, Page 35, Chippewa County Plats, surveyed by R.H. Larsen. Plat shows the section corner as the Point of Beginning of the subdivision.

1985 Northwoods Land Surveying, Job 450-00, recovered 4" square concrete monuments at the N.W. and S.W. corners of the Plat.

1987 W.L. Karr recorded corner in Liber 6, Page 394, Chippewa County Corner Records, as a 1" x 30" pipe with plastic cap no. 27450 set over a 4" square concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-9) Section Corner Common to Sections 24 & 25, T. 46 N., R. 1 E., and Sections 19 & 30, T. 46 N., R. 2 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found corner as recorded by Karr in 1987.

Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-9) Section Corner Common to Sections 24 & 25, T. 46 N., R. 1 E., and Sections 19 & 30, T. 46 N., R. 2 E.

Corner is a 1" o.d. pipe with cap no. 27450. Corner falls 7' South of centerline of 10 Mile Road.

Witnesses:	Utility Pole	N 18° E	44.20'
	Witness Pipe	S 52° E	62.64'
	Witness Pipe	S 68° W	71.67'
	8" Aspen	N 22° W	125.86'

Bearings are compass bearings, corrected for declination, distances to pole and aspen are to a nail and tag on the side of the witness object. Witness Pipes are 3/4" x 24" pipes with pipe caps set 1' below the surface.

Signed by

*William L. Karr*

Date

12-30-96

Surveyor's Michigan License No. 27450

