

MAY 28 1997

COMMISSION

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner

47.00 LAND CORNER

\$2.00 HSSR

2/28/1997 2:49:10 PM Receipt #21

RECEIVED FOR RECORD

CHIPPewa COUNTY - STATE OF MICHIGAN
 SHARON M. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 351

Register of Deeds Stamp & File Number

Chippewa County Located in: Corner Code #

1. Public Land Survey T46N R1E M-10 Same
 T46N R2E A-10 Corner
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. , Recorded Plat
 5. Private Claims

I, William L. Karr, in a field survey on December 3, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-10) 1/4 Corner Common to Section 25, T. 46 N., R. 1 E., and Section 30, T. 46 N., R. 2 E.

1845 J.H. Mullett set post in original survey.
 Witnesses: Tamarack 10" S 71° W 17 lks
 Tamarack 12" N 33° W 27 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-10) 1/4 Corner Common to Section 25, T. 46 N., R. 1 E., and Section 30, T. 46 N., R. 2 E.
 This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Could find no evidence of original survey or subsequent perpetuation of the corner position.

Supervisors Plat No. 1 of Bruce Township, Liber 7, Page 35, Chippewa County Plats, monumented the North 1/16th corner between sections 25 and 30. The North 1/4 mile is shown as 1329.1' on the plat.

The total mile measures 5316.36'. The Southwest corner of the plat is on the section line and at the proper distance from the section corner 19, 30, 24 & 25. Reestablished the 1/4 corner mid-way and on-line between the section corners to the North and the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-10) 1/4 Corner Common to Section 25, T. 46 N., R. 1 E., and Section 30, T. 46 N., R. 2 E.

Corner is a 3/4" x 24" re-rod with plastic Chippewa County Remonumentation Cap. Corner falls at the Northerly edge of a small area of dry ground surrounded by alder and submerged land. Corner is set 0.3' above grade.

Witnesses: Section Corner North 2658.19'
 4" Aspen S 14° E 64.92'
 Section Corner South 2658.19'
 4" Ash S 04° W 61.42'
 Metal Fence Post West 1.00'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

BOOK 9 PAGE 351

