

SURVEY &
REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:44

For corners in COMMISSION

Chippewa
(County)

Located In:

Corner Code ##

J. Roger Madsen
REGISTER OF DEEDS

1. Public Land Survey	T45N R 1E	M-1	Same
	T46N R 1E	M-13	Corner
	T45N R 2E	A-1	(Twp.
	T46N R 2E	<u>A-13</u>	Corner)
2. Property Controlling in Section	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1 (T45N, R2E)
Township Corner Common to T45N, R1E & T45N, R2E & T46N, R1E & T46N, R2E.

Original ties to post at township corner: Tamarack 10, N86°E 22 links
Tamarack 10, S36°W 10 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 (T45N, R2E)
This corner is being re-established as part of the Chippewa County Remonumentation Program.
Found no evidence of corner. Re-established corner 2640.00 feet west of the 1/4 corner between Section 6, T45N, R2E and Section 31, T46N, R2E, as shown in old County Surveyor notes. North-south position was established 33 feet south of remains of right-of-way fence on the north side of 12 Mile Road. Corner falls on the south edge of east-west gravel road (12 Mile Road), approximately 5 feet west of the centerline of gravel road to the south (Scenic Drive). East-west position also works well with found 1/4 corner between Section 1, T45N, R1E and Section 36, T46N, R1E.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 (T45N, R2E)
Corner is a 3/4" x 24" rebar with plastic Chippewa County Remonumentation cap at south edge of 12 Mile Road, 5' west of centerline of Scenic Drive to the south. Witnesses:

- 5" Tamarack, N35°W 74.20'
- 8" Tamarack, S57°E 73.07'
- 18" Spruce, S20°W 57.51'
- 4" Spruce, S74°W 68.74'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination. Distances are measured with EDM.

Recorded by Keith R. Waters Date 12-30-93

Surveyor's Michigan License No. 33142

