

**SURVEY & REMONUMENTATION**

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

MAR 09 1994

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:44

COMMISSION

For corners in  
**Chippewa**

(County)

Located In:

Corner Code #

*J. Roger Madsen*  
REGISTER OF DEEDS

1. Public Land Survey	T <u>45N</u> R <u>2E</u>	B-1	Same
	T <u>46N</u> R <u>2E</u>	B-13	Corner
	T _____ R _____		
	T _____ R _____		
2. Property Controlling In Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 (T45N, R2E) 1/4 Corner Common to Sec. 6, T45N, R2E & Sec. 31, T46N, R2E  
Original corner was a 10" Hemlock



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 (T45N, R2E)  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found a 4" diameter concrete monument approximately 1 foot north of centerline of east-west gravel road (12 Mile Road), approximately 4 feet east of the centerline of a ditch to the north. Monument is 33 feet south of remains of a right-of-way fence on the north side of 12 Mile Road. Monument is 6 inches below road surface and contains pieces of thin wire, which is consistent with other monuments found throughout Chippewa County. Accepted corner as found and established four witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 (T45N, R2E)  
Corner is 4" concrete monument 6" below gravel road surface, 1' north of centerline of 12 Mile Road), 4' east of centerline of ditch to the north.  
Witnesses:

- 8" Tamarack, N46°W 40.15'
- 6" Tamarack, N17°W 44.50'
- 10" Spruce, S49°E 75.89'
- 8" Maple, S14°W 45.44'

Note: Distances are to a nail and tag in the side of witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination. Distances are measured with EDM.

Signed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142

L 8 Pages 224