

2008 1939

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner

For corners in

**SECTION**

Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 46N R 2E

C-5

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

\$7.00 LAND CORNER

\$2.00 MSSR

21 JAN 1999 10:15:53 AM Receipt #13123

RECEIVED FOR RECORD

CHIPPewa COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK **10** PAGE **337**

Register of Deeds Stamp & File Number

I, Larry R. Rogers in a field survey on October 15, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		28		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C-5) Northeast Corner, Section 18, Township 46 North, Range 2 East.

The original corner was placed in 1845 by James H. Mullett. County Surveyor notes show 1 1/4" x 30" bolt with square head down and 6" x 4 1/2 foot cedar post. In 1922, the Section Corner is shown as the Point of Beginning for the Plat of "Clover Beach Subdivision" as recorded in Liber 4 of Plats at Page 6 of Chippewa County Records. A 1975 B.L.M. dependent resurvey found the 1 1/4" x 30" iron bolt and replaced with a 2 1/2" iron pipe with stamped brass cap set flush with ground. In 1982, William L. Karr, P.S. 27450 recovered the B.L.M. brass capped iron pipe and B.L.M. witnesses and filed a L.C.R.C. in Liber 6, Page 096 of the Chippewa County Corner Records. In 1992, Lawrence Weinreis, P.S. 32343 recovered same corner, added one new witness and filed a L.C.R.C. in Liber 7, Page 412 of the Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-5) Northeast Corner, Section 18, Township 46 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Recovered a B.L.M. 2 1/2" diameter iron pipe with stamped brass cap 2" below grade. Earlier 1 1/4" bolt is now 0.5 feet North of B.L.M. corner. Recovered three Weinreis witnesses and added two others. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-5) Northeast Corner, Section 18, Township 46 North, Range 2 East.

Corner is a B.L.M. 2 1/2" diameter iron pipe with stamped brass cap 2" below grade.

Witnesses:

14" Maple	N48°E	34.30 feet
10" Maple	N70°E	39.05 feet (previous 39.10 feet)
10" Triple Maple	S74°E	43.83 feet (previous 43.86 feet)
6" Twin White Birch	S01°E	23.30 feet (previous 23.34 feet)
Steel Fence Post	North	2.0 feet

Signed by [Signature] Date 30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.



BOOK **10** PAGE **337**