

DEC 18 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For corners in

Chippewa Located In: Corner Code #
1. Public Land Survey SAME CORNER T 46N R 2E D-1
T 47N R 2E D-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$7.00 LAND CORNER
\$2.00 HSSR
21 JAN 1999 10:19:01 AM Receipt #13123
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
BOOK 10 PAGE 342
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Larry R. Rogers in a field survey on October 15, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of C and 5. Handwritten 'E' and 'R' are visible near the grid.

A. Description of original monument and accessories and/or subsequent restoration:

(D-1) North 1/4 Corner of Section 5, Township 46 North, Range 2 East.

The original corner was placed in 1845 by James H. Mullett. 1895 County Surveyor notes give a distance of 2632 feet from 1/4 Corner to the Northwest corner of Section 5. In 1975 a B.L.M. dependent resurvey found and accepted a 1/2" rebar below the surface at the intersection of a gravel road (East and West) and an asphalt road to South. In 1981, William L. Karr, P.S. 27450 found a 1/2" iron pin that matched the position of the B.L.M. resurvey, and filed a L.C.R.C. in Liber 5, Page 072 of the Chippewa County Corner Records. Corner has since been used by several surveyors.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D-1) North 1/4 Corner of Section 5, Township 46 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found uncapped iron pin 4" below grade, in centerline of Six Mile Road (East-West, gravel) and on the extension of the centerline of Homestead Road to South. Position matches B.L.M. resurvey and Karr recording.

Distance West to Northwest corner of Section 5 is 2620.44 feet (2620.20 B.L.M.). Distance East to Northeast corner Section 5 is 39.6 feet short of B.L.M. distance, but recovered B.L.M. position at said Northeast corner. Believe B.L.M. distance recited on survey to be a blunder. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D-1) North 1/4 Corner of Section 5, Township 46 North, Range 2 East.

Corner is a 5/8" iron pin in centerline of 6 Mile Road and on the extension of the centerline of Homestead Road to South.

Witnesses:

Table with 3 columns: Witness description, Bearing, Distance. Includes 6" Aspen, Anchor Pole (new), Utility Pole (new).



Signed by [Signature] Date 30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.