

SECTION
 1999

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

For corners in

Chippewa County

Located in:

Corner Code #

1. Public Land Survey

T 46N R 2E

E-5

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

\$7.00 LAND CORNER

\$2.00 MSSR

21 JAN 1999 10:17:07 AM Receipt #1312

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 339

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers in a field survey on October 15, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3										8			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E-5) Northeast Corner, Section 17, Township 46 North, Range 2 East.

The original corner was placed in 1845 by James H. Mullett. County Surveyor records make no specific reference to corner. A 1975 B.L.M. dependent resurvey found and accepted a 1" diameter iron bar 4" below the surface of an East - West dirt road. In 1982, William L. Karr, found a 1 1/4" iron bar 6" below surface of East - West dirt road and filed a L.C.R.C. in Liber 6, Page 131 of the Chippewa County Corner Records. Corner has since been used in numerous surveys by several different surveyors.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-5) Northeast Corner, Section 17, Township 46 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found 1 1/4" iron bar 6" below grade and 7 feet South of centerline of 8 Mile Road (gravel). Recovered four witnesses from Karr recording. Brush lines to North and South. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-5) Northeast Corner, Section 17, Township 46 North, Range 2 East.

Corner is a 1 1/4" iron bar 6" below grade and 7 feet South of centerline of 8 Mile Road.

Witnesses:

6" Tamarack	N27°E	47.76 feet (new tag)
6" Spruce	N30°W	44.80 feet
Utility Pole (SUI/155/1)	S82°W	165.33 feet
18" Spruce	S71°E	122.54 feet (new tag)

Signed by


[Signature]

Date

30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995