

SURVEY & REMONUMENTATION

APR 27 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code H-5

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>2E</u> | <u>H-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
24 OCT 94 3:43 P.M. RECEIPT# 831
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on November 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5 1/4 Corner Common to Sections 10 & 15, T46N, R2E

Original ties to post: Black Ash 10, N73°W 27 links
Black Ash 8, S08°E 23 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 (T46N, R2E)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a fallen over wood post approximately 25 feet north of a fence corner, on line with a fence to the south. Right-of-way fences along east-west gravel road to the west (8 Mile Road) are approximately 50 feet apart. Post is 2643.82 feet east of Section corner to the west. Set a 3/4" rebar with a 3 1/4" aluminum cap in center of remains of base of post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 (T46N, R2E)

Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap approximately 25 feet north of a fence corner. Witnesses:

- 5" Black Ash, N24°E 16.63'
- 7" Black Ash, N76°E 9.58'
- 8" Black Ash, S29°W 26.41'
- 8" Willow, S54°W 27.15'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed painted. Bearings are compass bearings corrected for declination.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Keith R. Waters

Date 10-18-94

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISIONS: REVISED MAY 14, 1975
REVISED JAN., 1983

L8 Page 362