

SURVEY & REMONUMENTATION

DEC 09 1993

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC -3 PM 3:59

For corners in
Chippewa
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------------|
| 1. Public Land Survey | T <u>47</u> N R <u>1E</u> | <u>A-4</u> Same |
| | T <u>47</u> N R <u>1W</u> | <u>M-4</u> Corner |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters in a field survey on June 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4 (T47N, R1E)
1/4 Corner Common to Section 7, T47N, R1E and Section 12, T47N, R1W

This corner is recorded by James H. Granger, P.S. 16041, in liber 1, page 249, of Chippewa County corner records (1977) as a PK nail with the following ties:
Found bolt at fence corner, Due North 30.28'
South face of stop sign, N12°E 31.14'
PK in North side of Power Pole, S65°E 43.53'
Hydrant, S50°W 25.26'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 (T47N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found 1/2" iron at centerline of Meridian Street, 2.5' south of centerline of 8th Avenue. Power pole and hydrant remain from Granger records. Could not find PK in power pole, distance to center of pole fits well. Distance to center of top bolt on hydrant differs by 0.36' with Granger tie, but he does not specify what point on hydrant measurement was taken to. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 (T47N, R1E)
Corner is a 1/2" iron pin 2.5' south of centerline of 8th Avenue at centerline of Meridian Street.

Witnesses:

- Center of Top Bolt on Hydrant, S46°W 25.62'
- Power Pole, S60°W 38.38'
- 7" Aspen (Not blazed), N59°W 69.04'
- Power Pole, S60°E 43.32'

Note: Unless noted otherwise, distances to a nail and tag in the side of the witness object. Bearings are compass bearings corrected for declination. Distances measured with EDM.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by Keith R. Waters Date 11-30-93

Surveyor's Michigan License No. 33142