

SURVEY & REMONUMENTATION CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

DEC 09 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC -3 PM 3: 57

For corners in
Chippewa
(County)

Located In:	Corner Code #
T 47N R 1E	A-6 Same
T 47N R 1W	M-6 Corner
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28										
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on November 2, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 (T47N, R1E)
1/4 Corner Common to Section 18, T47N, R1E & Section 13, T47N, R1W.

Michigan State Highway Department (1965), as recorded in liber 2, page 248, of Chippewa County corner records: 1" iron pin with the following witnesses:
Metal Lamp Pole, N30°E 61.87' Metal Lamp Pole, N36°W 74.95'
PK Nail, Due South 31.35' Guard Post, S80°E 88.93'
Corner is shown on subsequent surveys as a wood hub with nail in monument box.
Witnesses: Light Pole, N05°W 29.02' Power Pole, S85°W 108.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 (T47N, R1E)
This corner is being re-established as part of the Chippewa County Remonumentation Program.
Wood hub with nail in monument box was destroyed during construction on the I-75 Business Spur in the summer of 1993. Monument box was replaced during construction in the wrong position. I contacted MDOT, who sent a crew to set a new box. Center of new box is approximately 1 foot from old box, which is now filled with concrete. Set a 3/4" rebar in new box using control from previous surveys in the area. Distance to an old nail with cap #24599 in a power pole is within 0.05' of record. Distance to center of light pole also checks well (no measuring nail found in light pole).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 (T47N, R1E)
Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in a monument box in the westerly lane of the I-75 Business Spur.
Witnesses:
Power Pole, S84°W 109.00' Note: Distance to poles is to a nail and tag in the side. Bearings are
Light Pole, N10°W 29.25' compass bearings corrected for
W'ly Bolt in Concrete Base of declination. Distances measured with
Gas Station Sign, NORTH 119.67' EDM.
Center of Top Nut on Hydrant, S83°E 78.87'

Signed by Keith R. Waters Date 11-30-93
Surveyor's Michigan License No. 33142