

SURVEY & REMONUMENTATION

DEC 09 1993

CHIPPEWA COUNTY REMONUMENTATION CORNER RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC -3 PM 3:58

COMMISSION

For corners in
Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 1E T 47N R 1W	A-9 Same M-9 Corner
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ *S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters in a field survey on November 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9 (T47N, R1E)

Section Corner Common to Secs. 19 & 30, T47N, R1E & Secs. 24 & 25, T47N, R1W.

This corner is recorded in liber 2, page 121, Chippewa County corner records, by Bancroft W. Bufe, R.L.S. 6152 (1955), as a 1 1/8" steel bolt set in a ditch with the following witnesses:

- 4" Poplar, S42°W 58.5'
- 3" Poplar, S60°W 40.0'
- Fence Post, South 30.0'
- 4" Poplar, S50°E 40.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 (T47N, R1E)

This corner is being re-established as part of the Chippewa County Remonumentation Program. This corner position was established several years ago by Northwoods Land Surveying, Inc. from remains of Bufe's witness objects, however actual corner position was never monumented. All traces of Bufe's witnesses are now gone. I established corner using traverse information obtained from Northwoods and found traverse points. Corner falls in the centerline of an east-west ditch off the southeast corner of a stand of Scotch Pines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 (T47N, R1E)

Corner is a 3/4" x 48" rebar with 3 1/4" Chippewa County Remonumentation cap in the centerline of an east-west ditch. Witnesses:

- 9" Scotch Pine, N48°W 60.39'
- 8" Scotch Pine, N12°W 47.13'
- 9" Scotch Pine, N04°E 54.81'
- 4" Black Spruce, N50°E 66.33'
- 1/2" Iron Rod, NORTH 17.08'

Note: Unless noted otherwise, distances are to a nail and tag in the side of witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted. Distances measured with EDM.

Signed by Keith R. Waters Date 11-30-93
Surveyor's Michigan License No. 33142

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													

