

MAR 27 1996 CHIPPEWA COUNTY REMONUMENTATION CORNER
 COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa Located In: Corner Code #
 (County)

1. Public Land Survey T47N R 1E C-11
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

\$ 7.00 LAND CORNER
 \$ 2.00 MSSR
 29 FEB 96 9:38 A.M. RECEIPT# 462
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON M. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William L. Karr, in a field survey on Dec. 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4		3		2		1	
3													
4	7	8				9		10		11		12	
5													
6	18	17				16		15		14		13	
7													
8	19					20		21		22		23	24
9													
10	30					29		28		27		26	25
11													
12	31					32		33		34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C-11) Section Corner 29, 30, 31 and 32, T47N R1E

1845: James H. Mullette set post

Witnesses: Fir 10" N33°W 15 links
 Fir 10" S59°E 26 links

? : R.H. Larsen found 3/8" iron pipe and cedar post. Corner was recorded in Liber 2, Page 197.

1990: K.R. Waters, P.S. 33142 found Railroad spike and accepted. Corner was recorded in Liber 7, Page 248.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(C-11) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found railroad spike as described by K.R. Waters in 1990. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-11) Corner is a railroad spike below pavement surface in centerline of 5 Mile Road, 3 feet East of centerline of Killackey Road to South.

Witnesses: 8" Scotch Pine N47°E 61.59' (existing)
 8" Scotch Pine S38°E 92.98' (existing)
 8" Scotch Pine S58°W 109.47'
 Corner Fence Post N02°E 45.60'



Signed by William L. Karr
 Surveyor's Michigan License No. 27450

Date 12/15/95

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted. FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT. 1995