

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T47N R 1E</u>	<u>E-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

\$ 7.00 LAND CORNER  
\$ 2.00 NSSR  
29 FEB 96 9:39 A.M. RECEIPT# 462  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on Dec. 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E-9) Section Corner 20, 21, 28 and 29, T47N, R1E  
1845: James H. Milette Fir 18" in diameter  
used for corner.

1976: N.D. Alix, P.S. 6254 set 1/2" iron with cap. Recorded corner in Liber 1, Page 214.

1991: L.E. Weinreiss P.S. 32343 re-established Alix corner position after road construction from existing survey control. Corner was recorded in Liber 7, Page 256.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-9) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found 1/2" iron with cap No. 32343 as described in 1991. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-9) Corner is a 1/2" iron with cap No. 32343. Corner falls approximately 3.5 feet East of centerline Shunk Road and on approximate centerline of main part of 4 Mile Road to East extended.

Witnesses: "V" Notch in North end of C.M.P. N70°E 25.45' (existing) WILLIAM L. KARR