

SURVEY & REMONUMENTATION

DEC 09 1993

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 CHIPPEWA COUNTY
 STATE OF MICHIGAN

93 NOV 31 AM 9:55

J. Roger Malotte
 REGISTER OF DEEDS

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>1E</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on July 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-13) South 1/4 Corner Section 33, T467-R1E

1840 William A. Burt, P.S., set post.

7" Fir N16°E 25 links
 5" Fir N66°E 18 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-13) This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Corner position was established on the extension of a fence line to the North, and on line between the Southwest and Southeast corners of Section 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-13) Corner is a 3/4" x 24" iron with stamped 2 1/2" diameter aluminum cap (Chippewa County Monumentation) P.S. 27450. Corner falls on the Northeast edge of drive into farm field to the Southeast. Falls 5' more or less East of extension of fence to South. Falls on extension of distant fence line to North. Falls 24' more or less South of centerline of extension of 6 Mile Road to West.

Witnesses: 10" Poplar N18°E 61.79'
 11" Elm N68°E 61.64'
 Wood corner fence post S04°W 99.07'
 "V" cut in North end C.M.P. N30°W 23.52'

Signed by William L. Karr Date 11/12/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
 Distances are to a nail in side of witness objects unless noted.

