

DEC 09 1993

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC -3 PM 3:57

For corners in  
Chippewa

(County)

Located In:

Corner Code **H-7**

1. Public Land Survey	T <u>47</u> N	R <u>1</u> E	<u>H-7</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

*J. Roger Malott*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters in a field survey on November 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-7 (T47N, R1E)  
1/4 Corner Common to Sections 15 & 22, T47N, R1E.

This corner is recorded in liber 7, page 197 (1989), by Larry R. Rogers, P.S. 29251, as a 3/4" iron with a 1 1/4" head in a monument box, with the following ties: Fire Hydrant (Top Nut), S60°E 35.12' 16" Ash, S08°E 110.00' NE corner attached garage foundation, S82°W 83.83' Power Pole (23/69), N28°W 90.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 (T47N, R1E)  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Monument box was paved over during reconstruction of Riverside Drive in 1990. Uncovered monument box and found a 3/4" iron with 1 1/4" square head as called for in previous recording. Distances to hydrant, power pole, and garage foundation all check within 0.06'. Could not find a measuring nail in Ash, distance to center checks well. Accepted corner position as found and raised monument box to surface of asphalt road by using an additional ring.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 (T47N, R1E)  
Corner is a 3/4" iron with a 1 1/4" square head in a monument box approximately 2.5' SW of the NE edge of asphalt pavement on Riverside Drive. Witnesses:

- Hydrant (Top Nut), S60°E 35.06'
- NE Corner Attached Garage Foundation, S82°W 83.89'
- Nail/tag #29251 in Power Pole (23/69), N28°W 90.27'
- Nail/tag in Power Pole (E-1), S01°E 79.28'

Note: Bearings are compass bearings corrected for declination. Distances are measured with EDM.

Signed by Keith R. Waters Date 11-30-93  
Surveyor's Michigan License No. 33142

