

SURVEY & REMONUMENTATION

DEC 09 1993

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

93 NOV 31 AM 9:54

J. Roger Malott
REGISTER OF DEEDS

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>1E</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William L. Karr, in a field survey on July 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-13) South 1/4 Corner Section 34, T47N-R1E

1840 William A. Burt, set post.
6" Hemlock N70°W 18 links
8" Hemlock N60°E 7 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-13) This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Corner position was reestablished on the extension of a very old fence to the North and on the split of remains of right-of-way fences for North-South position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-13) Corner is a 3/4" x 24" iron with stamped 2 1/2" diameter aluminum cap (Chippewa County Monumentation) P.S. 27450. corner falls in old grown up East-West road. Falls on extension of remains of very old fence to North.

Witnesses: 9" Aspen N10°E 59.65'
1/2" iron in drill hole in 4' x 4' boulder N60°E 86.64'
10" Maple N66°E 95.40'
10" Spruce S10°E 91.83'
11" Aspen S54°W 77.79'
Closing Corner West 7.50'

Signed by William L. Karr Date 11/12/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

