

RECORDS SECTION

JAN 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For corners in

Chippewa

Located In:

Corner Code #

- 1. Public Land Survey SAME CORNER T 47N R 1E M-2
T 47N R 2E A-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$7.00 LAND CORNER
\$2.00 MSSR
21 JAN 1999 11:03:56 AM Receipt #13123
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 368
Register of Deeds Stamp & File Number


4. Lot No. Recorded Plat
5. Private Claims

I, Larry R. Rogers, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains handwritten annotations 'E', 'R', 'N', 'H' and a dot in cell M1.

A. Description of original monument and accessories and/or subsequent restoration: (M-2) East 1/4 corner of Section 1, Township 47 North, Range 1 East. The original corner was placed in 1845 by John Mullett. Found no reference to corner in County Surveyor notes. In 1981, Granger Engineering showed the computed position of this corner to be midway and on-line between the Northeast and Southeast corners of Section 1, but no corner was set. The original G.L.O. notes call for 80.00 chains along the East line of Section 1.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (M-2) East 1/4 corner of Section 1, Township 47 North, Range 1 East. This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found no evidence of original corner position. Re-established corner position midway and on-line between the Northeast and Southeast corners of Section 1. Found old steel fence post 20 feet to Northwest of set corner. Unable to verify origin of fence post. Distances to corners North and South are 2634.58 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: (M-2) East 1/4 corner of Section 1, Township 47 North, Range 1 East. Corner is a 3/4" x 24" re-rod with stamped aluminum cap set in low, wet area Southwesterly of old field.

Witnesses table: 16" Spruce N11°E 50.56 feet, 8" Ironwood N40°W 15.02 feet, Steel Fence Post N47°W 19.67 feet, 12" Ash S78°W 5.56 feet, 6" Ash S79°E 26.45 feet, New Steel Fence Post North 2.0 feet



Signed by [Signature]

Date 30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.