

MAR 28 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For corners in

Chippewa Located In: Corner Code #
1. Public Land Survey SAME CORNER { T 47N R 1E M-5
T 47N R 2E A-5
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

\$7.00 LAND CORNER
\$2.00 HSSR
21 JAN 1999 10:26:56 AM Receipt #1312
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 351
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains handwritten numbers and letters like 'E', 'N', 'H'.

I, Larry R. Rogers, in a field survey on December 22, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(M-5) Southeast Corner of Section 12, Township 47 North, Range 1 East.

The original corner was placed in 1845 by John Mullett. County Surveyor records make no specific reference to this corner. In 1982, William L. Karr, P.S. 27450 re-established the corner position at a corner fence post (fences North and West), set a concrete monument and filed a L.C.R.C. in Liber 6, Page 117 of the Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(M-5) Southeast Corner of Section 12, Township 47 North, Range 1 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Corner is a 4" x 36" concrete monument with P.S. cap 27450. Remains of fence to North and West. Accepted corner position as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(M-5) Southeast Corner of Section 12, Township 47 North, Range 1 East.

Corner is a 4" x 36" concrete monument with P.S. cap 27450.



Witnesses:
Twin Maple N06°W 6.61 feet
15" Oak N79°W 43.88 feet
12" Oak S18°W 26.88 feet
7" Maple S26°E 32.43 feet

Signed by [Signature] Date 30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.