

DEC 18 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Chippewa County Remonumentation Corner

For corners in

SECTION

Chippewa

Located In:

Corner Code #

1. Public Land Survey **SAME CORNER** { T 47N R 1E  
T 47N R 2E  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_
3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

M-6 ✓  
A-6

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Larry R. Rogers, in a field survey on \_\_\_\_\_, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
(M-6) East 1/4 Corner of Section 13, Township 47 North, Range 1 East.

The original corner was place in 1845 by John Mullett. County Surveyor records make no specific mention of this corner. No other record of subsequent restoration has been recovered.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(M-6) East 1/4 Corner of Section 13, Township 47 North, Range 1 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found no evidence of original corner position. Found 1" iron pin 7.4 feet East and 20.6 feet North of a single property line position for 1/4 Corner. No history of 1" iron pin was recovered. Re-established corner position midway and on-line between Northeast and Southeast corners of said Section 13.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-6) East 1/4 Corner of Section 13, Township 47 North, Range 1 East.  
Corner is a 3/4" x 24" iron pin with stamped aluminum cap.

Witnesses:

5" Spruce	N16°W	15.52 feet
10" Maple	N20°E	28.70 feet
10" Maple	S06°E	26.17 feet
6" Maple	S36°W	28.87 feet
1" Iron Pin	N17°E	21.97 feet
Steel Fence Post	North	2.00 feet

Signed by [Signature] Date 30 Dec 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

\$7.00 LAND CORNER  
\$2.00 MSSR  
21 JAN 1999 10:28:01 AM Receipt #13123  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 352

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

