

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

SECTION

For corners in

Chippewa

Located In:

Corner Code #

- |                                    |             |                 |       |
|------------------------------------|-------------|-----------------|-------|
| 1. Public Land Survey              | SAME CORNER | T 47N R 1E      | M-9 ✓ |
|                                    |             | T 47N R 2E      | A-9   |
|                                    |             | T _____ R _____ |       |
|                                    |             | T _____ R _____ |       |
| 2. Property Controlling in Section | S _____     | T _____ R _____ |       |
|                                    | S _____     | T _____ R _____ |       |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____ R _____ |       |
|                                    | S _____     | T _____ R _____ |       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 21 JAN 1999 10:31:11 AM Receipt #13123  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 355  
 Register of Deeds Stamp & File Number

I, Larry R. Rogers, in a field survey on November 09, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(M-9) Southeast Corner of Section 24, Township 47 North, Range 1 East.

The original corner was placed in 1845 by John Mullett. In 1927, County Surveyor Colwell refers to Corner as "post in fence" and gives a distance of 2605 feet South to 1/4 Corner. 1935 County Surveyor notes refer to Corner as an iron pipe and oak post and gives a distance of 2616 feet South to 1/4 Corner. In 1981, William L. Karr, P.S. 27450 found 1" iron pipe and 2" x 2" wood post, set plastic cap inside pipe and filed L.C.R.C. in Liber 5, Page 146 of the Chippewa County Corner Records. Distance South to 1/4 Corner now measures 2615.55 feet.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M-9) Southeast Corner of Section 24, Township 47 North, Range 1 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1" iron pipe with P.S. cap number 27450 and recovered four Karr witnesses - one now dead. Accepted corner position as found.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M-9) Southeast Corner of Section 24, Township 47 North, Range 1 East.

Corner is a 1" iron pipe with P.S. cap number 27450.

**Witnesses:**

16" Ash	N37°W	8.84 feet
6" Oak	S11°W	3.00 feet
5" Ash	S37°E	17.35 feet
8" Ash	N46°E	32.90 feet
Steel Fence Post	North	2.0 feet



Signed by \_\_\_\_\_ Date 30 DEC 1998

Surveyor's Michigan License No. 29251

**NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.**